DESCRIPTION	UNIT	QTY	RATE	AMOUNT
Provisional Bill Of Quantities				
BILL NO. 01				
DEMOLITIONS				
<u>PREAMBLES</u>				
The Tenderer is referred to the relevant Clauses in the separate document The Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated at the front of these Bills of Quantities.				
<u>View site</u>				
Before submitting his or her tender the tenderer shall visit the site and satisfy himself or herse as to the nature and extent of the work to be done and the value of the materials contained in the fencing of site. No claim for any variations of the contract sum in respect of the nature an extent of the work or of inferior or damaged materials will be entertained				
REMOVAL OF EXISTING WORK				
Taking down and removing				
Steel wire mesh fence 2,1m high including digging out steel poles	m	157		
5m steel gate	no	2		
Carried to Summa	ry			
BILL NO. 02				
<u>EARTHWORKS</u>				
PREAMBLES				
The Tenderer is referred to the relevant Clauses in the separate document The Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated at the front of these Bills of Quantities.				
Site clearance etc:				
Allow for clearing the area of the site to be built upon of all grass, weeds, shrubs, trees with trunks not exceeding 200mm girth, debris, etc., including grubbing up all roots, scoffling up as required and cart away all vegetation and debris.	m²	157		

EXTERNAL WORKS PREAMBLES The Tenderer is referred to the relevant Clauses in the separate document The Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated at the front of these Bills of Quantities. FENCING AND GATE Clear view standard density anti-climbing and anti-cut pressed galvanised razor mesh panel fencing with aperture size 76mm x 25mm and reinforcing V-section ribs, bolted with vandal resistant bolts and clamping plates to galvanised 85 - 45mm Taper locking post including Locking Recess Mechanism at 3,382m centres with sealed end caps and 30 x 3mm x 250mm long angle section base anchors with posts bedded in 15MPa concrete bases size 400 x 400 x 600mm deep with bitumen coated 400mm ClearVu underdig, all to Manufacturer's specification: Fencing 2 100mm high fencing	n 15		
PREAMBLES The Tenderer is referred to the relevant Clauses in the separate document The Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated at the front of these Bills of Quantities. FENCING AND GATE Clear view standard density anti-climbing and anti-cut pressed galvanised razor mesh panel fencing with aperture size 76mm x 25mm and reinforcing V-section ribs, bolted with vandal resistant bolts and clamping plates to galvanised 85 - 45mm Taper locking post including Locking Recess Mechanism at 3,382m centres with sealed end caps and 30 x 3mm x 250mm long angle section base anchors with posts bedded in 15MPa concrete bases size 400 x 400 x 500mm deep with bitumen coated 400mm ClearVu underdig, all to Manufacturer's specification: Fencing 2 100mm high fencing	n 15		
The Tenderer is referred to the relevant Clauses in the separate document The Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated at the front of these Bills of Quantities. FENCING AND GATE Clear view standard density anti-climbing and anti-cut pressed galvanised razor mesh panel fencing with aperture size 76mm x 25mm and reinforcing V-section ribs, bolted with vandal resistant bolts and clamping plates to galvanised 85 - 45mm Taper locking post including Locking Recess Mechanism at 3,382m centres with sealed end caps and 30 x 3mm x 250mm long angle section base anchors with posts bedded in 15MPa concrete bases size 400 x 400 x 500mm deep with bitumen coated 400mm ClearVu underdig, all to Manufacturer's specification: Fencing	n 15		
Preambles for Trades 2008 published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated at the front of these Bills of Quantities. FENCING AND GATE Clear view standard density anti-climbing and anti-cut pressed galvanised razor mesh panel fencing with aperture size 76mm x 25mm and reinforcing V-section ribs, bolted with vandal resistant bolts and clamping plates to galvanised 85 - 45mm Taper locking post including Locking Recess Mechanism at 3,382m centres with sealed end caps and 30 x 3mm x 250mm long angle section base anchors with posts bedded in 15MPa concrete bases size 400 x 400 x 500mm deep with bitumen coated 400mm ClearVu underdig, all to Manufacturer's specification: Fencing 2 100mm high fencing	n 15		
Clear view standard density anti-climbing and anti-cut pressed galvanised razor mesh panel fencing with aperture size 76mm x 25mm and reinforcing V-section ribs, bolted with vandal resistant bolts and clamping plates to galvanised 85 - 45mm Taper locking post including Locking Recess Mechanism at 3,382m centres with sealed end caps and 30 x 3mm x 250mm long angle section base anchors with posts bedded in 15MPa concrete bases size 400 x 400 x 600mm deep with bitumen coated 400mm ClearVu underdig, all to Manufacturer's specification: Fencing 2 100mm high fencing	n 15		
fencing with aperture size 76mm x 25mm and reinforcing V-section ribs, bolted with vandal resistant bolts and clamping plates to galvanised 85 - 45mm Taper locking post including Locking Recess Mechanism at 3,382m centres with sealed end caps and 30 x 3mm x 250mm long angle section base anchors with posts bedded in 15MPa concrete bases size 400 x 400 x 500mm deep with bitumen coated 400mm ClearVu underdig, all to Manufacturer's specification: Fencing 2 100mm high fencing	n 15		
2 100mm high fencing m	n 15	157	
	n 15	157	
Sates		157	
Jules .			
Vehicular gate size 5 000 x 2 100mm, double leaf swing	No	1	
Carried to Summary			
SUMMARY OF SCHEDULES			
DEMOLITIONS	BILL No.	1	
EARTHWORKS	BILL No.	2	
EXTERNAL WORKS	BILL No.	3	
SUB - TOTAL			
ADD VAT @ 15%			